

TOWN OF SOUTHWEST RANCHES, FLORIDA
Southwest Ranches Drainage Project
IFB No. 19-002
Thursday, April 25, 2019

ADDENDUM 3

1. **Question:** Is the Town requiring an Environmental Pollution Insurance (page 64)?

Answer: Confirming that the Town does require environmental pollution insurance as stated on page 64.

2. **Question:** Bid item #8 indicates (9) "Furnish and Install Ditch Bottom Inlet Type C" however the plans account for (11) not (9). Please clarify the correct quantity.

Answer: Bid Item #8 should include (11) "Furnish and Install Ditch Bottom Inlet Type C".

3. **Question:** Bid item #10 indicates (1) "Furnish and Install Ditch Bottom Inlet Type F" work element #4 however we cannot find this item on the plans. Please indicate where this item is.

Answer: There is no "Type F Inlet" proposed as part of work element #4. Therefore, Bid Item #10 should be excluded from the Bid Schedule. Please utilize newly attached bid schedule on page 2 of this addendum for work element 1,3,4,5.

4. **Question:** Plan page CP-102 work element #3 shows a Type D Inlet #5 with PRB (baffle) on west invert however this item is not listed on the bid items. Please confirm if this item is to be included and where.

Answer: Please see detailed response in addendum 2, question 4, issued on April 16, 2019.

5. **Question:** Please provide soil report for the project.

Answer: There is no soil report available for this project.

6. **Question:** For Work Element #1, 3, 4, 5, bid item #15 indicates 333 s/y of "Pavement Restoration", since this item is for driveway / road restoration is it possible to keep the areas with lime rock in place and complete all the asphalt patching at one time?

Answer: If base course is to be exposed to general traffic prior to final asphalt surface being applied, the cover material shall comply with section 300-2.2 of the standard specifications.

TOWN OF SOUTHWEST RANCHES, FLORIDA
SOUTHWEST RANCHES DRAINAGE PROJECT
IFB No. 19-002

BID SCHEDULE

The undersigned hereby proposes to furnish all labor, equipment and materials necessary to complete the work in strict accordance with the contract documents, schedules and plans, and all addenda, if issued, for the lump sum price shown below.

Bid and Proposal Form Includes Quantities for:

SW 136th Avenue north of SW 55th Street - Work Element 1

SW 54th Place west of SW 188th Avenue - Work Element 3

SW 178th Avenue at SW 46th Street - Work Element 4

SW 202nd Avenue north of SW 48th Street - Work Element 5

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
1	Mobilization	1	LS	\$ _____	\$ _____
2	Maintenance of Traffic	1	LS	\$ _____	\$ _____
3	Testing	1	LS	\$ _____	\$ _____
4	NPDES Best Management Practices (BMP)	1	LS	\$ _____	\$ _____
5	Furnish and Install Tree Protection Fencing	1407	LF	\$ _____	\$ _____
6	Furnish and Install 18" RCP Drainage Pipe	276	LF	\$ _____	\$ _____
7	Furnish and Install 24" RCP Drainage pipe	208	LF	\$ _____	\$ _____
8	Furnish and Install Ditch Bottom Inlet "Type C"	11	EA	\$ _____	\$ _____
9	Furnish and Install Ditch Bottom Inlet "Type D" work element #3	1	EA	\$ _____	\$ _____
10	Furnish and Install Ditch Bottom Inlet "Type F" work element #4	1	EA	\$ _____	\$ _____
11	Furnish and Install Headwall, Per FDOT "Index No.250"	1	EA	\$ _____	\$ _____
12	Rebuild Concrete Rip-Rap Headwall per CBWCD work element #1	1	LS	\$ _____	\$ _____
13	Core drill proposed invert into exist. drainage structure	2	EA	\$ _____	\$ _____

TOWN OF SOUTHWEST RANCHES, FLORIDA
 SOUTHWEST RANCHES DRAINAGE PROJECT
 IFB No. 19-002

14	Clean and clear 36" culvert work element #1	1	LS	\$ _____	\$ _____
15	Pavement Restoration	333	SY	\$ _____	\$ _____
16	Furnish and Install Gravel driveway	61	CY	\$ _____	\$ _____
17	Excavate Proposed Swale in Accordance with contract plans.	1754	SY	\$ _____	\$ _____
18	Furnish and Install Grass Sod, Bahia.	787	SY	\$ _____	\$ _____
19	Furnish and Install 6" Pavement Markings Yellow	50	LF	\$ _____	\$ _____
20	Furnish and Install 24" Thermoplastic Stop bar	11	LF	\$ _____	\$ _____

Total for Work Elements 1, 3, 4, 5: _____